



# WHITACRE GREER COMPANY

|  | WT.  | PCS/SQ.FT. | PCS/PALLET SQ. | FT/PALLET | WT/PALLET |
|--|------|------------|----------------|-----------|-----------|
| 4 x 8 x 1-1/2  | 3.8  | 4.5        | 702            | 156       | 2727#     |
| 4 x 8 x 2-1/4  | 5.5  | 4.5        | 486            | 108       | 2733#     |
| 4 x 8 x 2-3/4  | 7.2  | 4.5        | 378            | 84        | 2787#     |
| 8 x 8 x 2-1/4  | 11.1 | 2.25       | 216            | 96        | 2463#     |
| 8 x 8 x 2-3/4  | 14   | 2.25       | 168            | 75        | 2417#     |
| 3-5/8 x 7-5/8 x 1-1/4 *  | 2.8  | 4.5        | 960            | 213       | 2753#     |
| 3-5/8 x 7-5/8 x 2-1/4 *  | 5.1  | 4.5        | 540            | 120       | 2819#     |
| <b>* MODULAR PAVERS SET IN MORTAR WITH 3/8-INCH MORTAR JOINT</b> |      |            |                |           |           |
| 6 x 3 x 2-1/4  | 3.2  | 8          | 1016           | 127       | 3311#     |
| 6 x 3 x 2-3/4  | 4.1  | 8          | 696            | 87        | 2913#     |
| 6 x 6 x 2-1/4  | 6.3  | 4          | 508            | 127       | 3260#     |
| 6 x 6 x 2 3/4  | 8.1  | 4          | 348            | 87        | 2880#     |
| 6 x 9 x 2 1/4  | 9.3  | 2.7        | 344            | 127       | 3258#     |
| 6 x 9 x 2 3/4  | 12.5 | 2.7        | 256            | 94        | 3260#     |
| 2 1/4 x 9 x 2 1/4 ***  | 3.5  | 7.1        | 800            | 113       | 2865#     |
| 2 1/4 x 9 x 3 ***  | 4.6  | 7.1        | 672            | 95        | 3156#     |
| 3 x 9 x 3 ***  | 6    | 5.3        | 512            | 97        | 3137#     |
| MASONRY SPLITS<br>3 5/8 x 7 5/8 x 1 1/4 ****                     | 2.8  | N/A        | 780            | N/A       | 2200#     |

**\*\*\*\* MASONRY SPLITS ARE PACKAGED IN CUBES - 5 STRAPS OF 156 PIECES PER STRAP**

